

## 2 Off-site manufactured materials, components or buildings

Drawings that must accompany this section of measurement.		<ol style="list-style-type: none"> <li>1 Site plans.</li> <li>2 Plans.</li> <li>3 Sections.</li> <li>4 Elevations.</li> <li>5 Installation details.</li> </ol>	<b>Mandatory information to be provided.</b>	<ol style="list-style-type: none"> <li>1 Kind and quality of materials.</li> <li>2 Method of fixing or installing.</li> <li>3 Connecting to other work and services.</li> <li>4 Special finishes.</li> </ol>	<b>Notes, comments and glossary</b>
Minimum information that must be shown on the drawings that accompany this section of measurement.		<ol style="list-style-type: none"> <li>1 Major dimensions of component, structure or unit.</li> <li>2 Location of component, structure or unit.</li> </ol>	<b>Works and materials deemed included.</b>	<ol style="list-style-type: none"> <li>1 All factory applied finishes.</li> <li>2 Transport from factory to site.</li> <li>3 Offloading and storing on site.</li> <li>4 Setting, hoisting and placing in final position.</li> <li>5 All connection and joint materials.</li> <li>6 All service connections.</li> <li>7 Disposal of all packaging and protective materials.</li> </ol>	
<b>Item or work to be measured</b>	<b>Unit</b>	<b>Level one</b>	<b>Level two</b>	<b>Level three</b>	<b>Notes, comments and glossary</b>
Component	nr	<ol style="list-style-type: none"> <li>1 Overall dimensions.</li> </ol>	<ol style="list-style-type: none"> <li>1 Description of component.</li> </ol>	<ol style="list-style-type: none"> <li>1 Method of fixing/installing.</li> <li>2 Height above structural ground floor level.</li> <li>3 Services connections.</li> </ol>	<ol style="list-style-type: none"> <li>1 These are prefabricated proprietary components that are not adequately covered by the other Work Sections in this document.</li> </ol>

Item or work to be measured	Unit	Level one	Level two	Level three	Notes, comments and glossary
2 Prefabricated structures	nr	1 Overall dimensions.	1 Roofs. 2 External walls. 3 Internal walls/partitions. 4 Floors. 5 Stairs. 6 Bridges. 7 Masts. 8 Other, type stated.		1 These are complete or substantially complete building elements of proprietary construction, largely prefabricated. The fixing of items supplied only as part of the proprietary package is included here. Other work not forming part of the proprietary package is measured separately in the appropriate Work Section.
3 Prefabricated building units	nr		1 Toilet/bathroom units. 2 Sound proof rooms. 3 Cold rooms. 4 Spray booths. 5 Kiosks. 6 Other, type stated.		1 These are complete or substantially complete room units, usually of proprietary construction, for incorporation into buildings, structures or siteworks. The list is not exhaustive.
4 Prefabricated buildings	nr		1 Description of building.		1 These are complete or substantially complete building superstructures of proprietary construction, largely prefabricated. The fixing of items supplied only as part of the proprietary package is included here. Other work not forming part of the proprietary package is measured separately in the appropriate Work Section.