

Room Schedule			
Name	Ceiling Finish	Floor Finish	Wall Finish
Cloaks	9.5mm plaster base board and skim. 3cts emulsion	19mm terrazzo	13mm 2 coat lightweight gypsum plaster. 3cts emulsion paint. 25 x 100mm oil painted softwood skirting
Customs Officers	9.5mm plaster base board and skim. 3cts emulsion	25mm oak blocks	13mm 2 coat lightweight gypsum plaster. 3cts emulsion paint. 25 x 100mm oil painted softwood skirting
General Office	9.5mm plaster base board and skim. 3cts emulsion	5mm thermoplastic tiles. 150 x 150mm	13mm 2 coat lightweight gypsum plaster. 3cts emulsion paint. 25 x 100mm oil painted softwood skirting
Reception	9.5mm plaster base board and skim. 3cts emulsion	150 x 150 x 16mm red quarries	13mm 2 coat lightweight gypsum plaster. 3cts emulsion paint. 25 x 100mm oil painted softwood skirting
Waiting	9.5mm plaster base board and skim. 3cts emulsion	3mm rubber tiles. 300 x 300mm	13mm 2 coat lightweight gypsum plaster. 3cts emulsion paint. 25 x 100mm oil painted softwood skirting

### Finishes Schedule

Project number Asgnmt 1

Date Jan. 2007

Drawn by Author

Checked by Checker

Scale

A102